



03-Jun-2025

TO: Revision: 0

Ministry of Defence

PROJECT: WORKSHOP AT MAM

SUBJECT: Supply of AHU, ACCU and FCU

Dear Sir,

We thank you for inviting us to quote for the subject stated above. We are pleased to submit our most competitive techno-commercial bid for the subject project as under-

Scope of Work

Page 1 of 4 truebook





03-Jun-2025

TO: Revision: 0

Ministry of Defence

PROJECT: WORKSHOP AT MAM

SUBJECT: Supply of AHU, ACCU and FCU

Dear Sir.

We thank you for inviting us to quote for the subject stated above. We are pleased to submit our most competitive techno-commercial bid for the subject project as under-

Air Handling unit CLCP

- Casing External: 0.5mm Powder Painted Galvanized Steel/ Stainless Steel SS304.
- * Casing Internal: 0.5mm Galvanized Steel/ Stainless Steel SS304.
- * Complete fan and motor assembly is mounted on spring isolators.
- * Cooling coil section: Copper tubes and Aluminium fins suitable for chilled water system with chilled water IN/OUT = 6/12 deg C.
- * Cooling coil section: Copper tubes and Aluminium fins suitable for Dx system with Refrigerant R410a/R407c.
- * Drain pan: Stainless Steel SS304.
- * Eurovent Certified.
- * FAHU Shall be provided with Heat Recovery Wheels as per the given schedule.
- * FAHU shall be supplied with Heat Pipe as per the given schedule.
- * Fan motors: shall be VFD compatible high efficiency IE3 Type [VFD excluded]
- * Fan section: with Statically & Dynamically balanced Double Inlet Double Width Belt Driven Centrifugal Fan with constant pitch pulley/ plug fans with VFD/ Variable Speed high efficiency EC fans (SISW).
- * Filter Section: 2" flat filter of grade G3 + 15" Bag filters of grade F7 as per EN779.
- * H13 Hepa filter section as the given schedule.
- * Insulation: 50mm thick pressure injected polyurethane foam (PUF) insulation.
- * Mixing/Inlet section: With standard motorizable damper [Actuator excluded]
- * Panels: Double skin, rigid and totally enclosed casing with thermal barrier.
- * Roof canopy: Provided for external/ roof mounted units.
- * The proposal has given based on attached selection and drawings.





03-Jun-2025

TO: Revision: 0

Ministry of Defence

PROJECT: WORKSHOP AT MAM

SUBJECT: Supply of AHU, ACCU and FCU

Dear Sir.

We thank you for inviting us to quote for the subject stated above. We are pleased to submit our most competitive techno-commercial bid for the subject project as under-

- * Thyristor controllable Electric heater section as per the given schedule (Thyristor Excluded)
- * UV section with UV lamps as per the given schedule.

Fan Coil unit HFCF

- * 3-speed motor, selected at medium speed
- * 6 mm nylon filter or 20 mm aluminum filter
- Centrifugal fan with statically and dynamically balanced forward-curved blades
- * Cooling coil with copper tubes and aluminum fins
- Galvanized steel or stainless steel drain pan
- Trane chilled water single skin fan coil unit, Made in PRC

Payment Terms

100% through LC 120 Days from delivery note date and UPAS payable at sight.

Des	cription	Model	Quantity	Rate	Amount
Equipments					
Air Handling unit		CLCP004	1	2472.54	2,472.540
Air Handling unit		CLCP03A	1	2228.03	2,228.030
Air Handling unit		CLCP014	2	2975.77	5,951.540
Air Handling unit		CLCP007	3	2233.09	6,699.276
Air Handling unit		CLCP012	1	2761.64	2,761.640
Air Handling unit		CLCP005	1	1960.98	1,960.980
Air Handling unit		CLCP004	1	1828.68	1,828.680
Air Handling unit		CLCP018	1	4338.46	4,338.460





03-Jun-2025

Air Cooled Condensing Unit	RAUP500	1	9214.95	9,214.950
Fan Coil unit	HFCF10_3R	18	192.83	3,470.976
Fan Coil unit	HFCF12_3RE	7	212.24	1,485.652

Terms and Conditions:

- * This quotation is valid for a period of 10 days from the date of issue.
- * Prices quoted are inclusive of applicable taxes and duties unless otherwise stated.
- * Installation is included in the quotation. If included, it must be scheduled in advance.

Total	42,412.724		
VAT %5.00	2,120.636		
Grand Total	44,533.360		

in Words: OMR: Forty-Four Thousand Five Hundred Thirty-Three And Thirty-Six Baiza Only

Validity:

30 days hereof

Delivery:

Within 16 to 18 weeks to our store from the date of confirmed order and receipt of letter of credit.

Warranty

Air Cooled Condensing Unit Unit Warranty

18 months from date of shipment or 12 months from date of commissioning which ever ends earlier.

Air Handling unit Unit Warranty

18 months from date of shipment or 12 months from date of commissioning which ever ends earlier.

Fan Coil unit Unit Warranty

18 months from date of shipment or 12 months from date of commissioning which ever ends earlier.

Exclusions

Thank you for your interest in our [products/services]. We are pleased to submit our quotation as follows:

Page 4 of 4 truebook